DOCUMENT RESUME

ED 446 415 EF 005 622

TITLE	Florida Educational Facilities, 1997.
INSTITUTION	Florida State Dept. of Education, Tallahassee. Office of Educational Facilities.
PUB DATE	1997-00-00
NOTE	88p.; For related documents on Florida Educational Facilities, see EF 005 621-23.
PUB TYPE	Reports - Descriptive (141)
EDRS PRICE	MF01/PC04 Plus Postage.
DESCRIPTORS	Construction Costs; *Educational Facilities Design; Elementary Secondary Education; Flooring; *Interior Design; *Public Schools; Roofing; *School Construction; Site Development
IDENTIFIERS	Floor Plans; *Florida

ABSTRACT

This document contains information, photographs, and floor plans of many of Florida's new elementary through high school facilities occupied in 1997. Each entry lists the facility's type, building size, student capacity, and general structural information. Also provided is information on the facility's total construction cost; the architects and construction company used; special features of the facility; site development; and the interior components, including roofing, walls, floor finishes, electrical, heating and air conditioning, and plumbing. (GR)

Reproductions supplied by EDRS are the best that can be made
from the original document.

ED 446 415



PERMISSION TO REPRODUCE AND DISSEMINATE THIS MATERIAL HAS BEEN GRANTED BY

Suzanne Marshall

TO THE EDUCATIONAL RESOURCES INFORMATION CENTER (ERIC)

FLORIDA EDUCATIONAL FACILITIES 1997

EF 005 622

U.S. DEPARTMENT OF EDUCATION
Office of Educational Research and Improvement
EDUCATIONAL RESOURCES INFORMATION CENTER (ERIC)

This document has been reproduced as received from the person or organization originating it.

Minor changes have been made to improve reproduction quality.

Points of view or opinions stated in this document do not necessarily represent official OERI position or policy.

BEST COPY AVAILABLE

INTRODUCTION

The office of Educational Facilities receives many request for information concerning recently constructed schools and community college facilities. This publication is prepared in response to these requests.

Contained within is pertinent information including photographs and floor plans of many of Florida's newest educational facilities occupied in 1997. It is our intent that this document serve as a valuable resource for the purpose of assisting in the complex process of planning educational facilities.

Appreciation is extended to those school district and community college staff, and their consultants who provided the information for this publication, as well as to those who contributed many hours to its development and publishing.

Your comments and suggestions are always encouraged.

Wayne V. Pierson
Deputy Commissioner for
Planning, Budgeting, and Management

Introduction

Everglades City School
Collier County Public Schools 6

Coral Reef Senior High School
Miami-Dade County Public Schools 8

Howard A. Doolin Middle School
Miami-Dade County Public Schools 10

Eneida Massas Hartner Elementary School
Miami-Dade County Public Schools 12

Primary Learning Center A
Miami-Dade County Public Schools 14

Primary Learning Center B
Miami-Dade County Public Schools 16

Primary Learning Center C
Miami-Dade County Public Schools 18

Primary Learning Center D
Miami-Dade County Public Schools 20

Laura C. Saunders Elementary School
Miami-Dade County Public Schools 22

Edward L. Whigham Elementary School
Miami-Dade County Public Schools 24

Indian Trails K-8 School
Flagler County Public Schools 26

Bell Elementary School
Gilchrist County School District 28

Clewiston Middle School
Hendry County Public Schools 30

Hill-Gustat Middle School
Highlands County Schools 32

Gordon Burnett Middle School
Hillsborough County Public Schools 34

Walter L. Sickles High School
Hillsborough County Public Schools 36

Williams Middle School
Hillsborough County Public Schools 38

Carlos E. Haile Middle School
Manatee County School Board 40

Greenway Elementary - Southeast
Elementary School "K"
Marion County School District 42

Antioch Elementary School
Okaloosa County School District 44

Davidson Middle School
Okaloosa County School District 46

Destin Middle School @ Regatta Bay
Okaloosa County School District 48

Discovery Middle School
Orange County Public Schools 50

TABLE OF CONTENTS

Lake Whitney Elementary School "R"
Orange County Public Schools 52

Rosemont Elementary School "T"
Orange County Public Schools 54

Southwood Elementary School "S"
Orange County Public Schools 56

Sunrise Elementary School
Orange County Public Schools 58

Celebration School
Osceola County Public Schools 60

Kissimmee Middle School
Osceola County Public Schools 62

Brooker Creek Elementary School
Pinellas County Schools 64

McMullen Booth Elementary School
Pinellas County Schools 66

John M. Sexton Elementary School
Pinellas County Schools 68

Wicklow Elementary School
Seminole County Public Schools 70

Building Number 6
Daytona Beach Community College 72

L. Gale Lemerand Health, Wellness, & Community Education Center
Daytona Beach Community College 74

New Community College Center
Edison Community College 76

William A. Seeker Campus
Florida Keys Community College 78

Martin and Pat Fine Center for the Arts
Miami-Dade Community College 80

Teaching Zoo
Santa Fe Community College 82

Student Services Building
Valencia Community College 84

Appendices 86

EVERGLADES CITY SCHOOL
COLLIER COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: Replacement Pre-K - 12 School
FACILITY NAME & ADDRESS:
Everglades City Schools
499 School Drive
Everglades City, FL 34139
(941) 695-2561
OWNER, CONTACT PERSON & PHONE NUMBER:
Collier County Public Schools
David Lesansky
5704 Cougar Lane
Naples, FL 34109
(941) 514-2681
ARCHITECT, ADDRESS & PHONE NUMBER:
Schenkel Shultz
8250 College Parkway
Ft. Myers, FL 33919
(941) 481-0200
CONTRACTOR, ADDRESS & PHONE NUMBER:
Kraft Construction
2606 S. Horseshoe Drive
Naples, FL 34104
(941) 643-6000
CONSTRUCTION CONTRACT DATE: January 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 8.5 Acres
BUILDING AREA: 81,000 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 12
STUDENT CAPACITY: 415
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable):
$10,681,070

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 16 Classrooms, 2 Skills Labs, 2 Resource Rooms, 2 Science Labs, 3 ESE Classrooms, Art, Music, 1 Vo-tech Lab, Gym, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: All areas are available for community use.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, baseball field, basketball courts, landscaping, and courtyards.
FLOORS: Concrete topping on hollow core slabs on piling.
ROOF: Metal roofing on a pre-engineered rigid frame.
EXTERIOR WALLS: Concrete masonry units with integral colored block veneer.
INTERIOR WALLS: Concrete masonry units and metal studs, gypsum board, and veneer plaster.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Rubber, ceramic tile, and quarry tile.
CEILINGS: 2x2 lay-in acoustical tile, gypsum board, and exposed.
HVAC: Chilled water system, VAV boxes, individual units, and heat recovery.
PLUMBING: Municipal water and sewer. Copper water distribution pipes and PVC sewage drainage system. Fire sprinkler system at stage.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, fiber optics, computer networking, and energy management.


PLAYGROUND
CLASSROOMS
STAGE
DINING
KITCHEN
PLAYGROUND
VO-TECH
MEDIA
COURT YARD
MUSIC
MAIN ENTRANCE
ART
LOCKERS
ADMIN.
GYM
CLASSROOMS

CORAL REEF SENIOR HIGH SCHOOL
MIAMI-DADE COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New High School
FACILITY NAME & ADDRESS:
Coral Reef Senior High School
10101 S.W. 152 Street
Miami, FL 33176
(305) 232-2044
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade County Public Schools
Ivan M. Rodriquez
1450 N.E. 2 Avenue, Suite 569
Miami, FL 33132
(305) 995-4500
ARCHITECT, ADDRESS & PHONE NUMBER:
Mateu Carreno Rizo and Partners, Inc.
232 Minorca Avenue
Coral Gables, FL 33134
(305) 441-0888
CONTRACTOR, ADDRESS & PHONE NUMBER:
Andrade Gutierrez Construction, Inc.
7270 N.W. 12 Street
Miami, FL 33126
(305) 591-9765
CONSTRUCTION CONTRACT DATE: January 1995
OCCUPANCY DATE: October 1997
SITE SIZE: 60 Acres
BUILDING AREA: 295,399 Sq. Ft.
GRADE LEVEL ORGANIZATION: 9 - 12
STUDENT CAPACITY: 2,657
TOTAL CONSTRUCTION COST: (includes site improve., site aquisition, furn & equip, & fees as applicable):
$46,323,062

GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 40 Classrooms, 8 Resource Rooms, 9 Skills Labs, 11 Science Labs, 4 ESE Classrooms, 3 Art Labs, 5 Music Labs, 16 Vo-tech Labs, Gym, Administration, Library/Media, Auditorium, Stage, Dining, and Kitchen.
SPECIAL FEATURES or COMMENTS: Magnet school for medicine, international finance, math, public service, arts, and agriculture.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, softball field, basketball courts, tennis courts, landscaping, and courtyards
FLOORS: Concrete slab on grade, second floor poured concrete.
ROOF: Built up roof on precast concrete deck.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Metal studs with gypsum board.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl, ceramic tile, and quarry tile.
CEILINGS: 2x2 lay-in acoustical tile and plaster.
HVAC: Air cooled chiller and cooling tower.
PLUMBING: Municipal water and sewer.
ELECTRICAL: Fluorescent and HID light fixtures. Telephone, CCTV, fire alarm, intercom, security, emergency generator, computer networking, and energy management.



9

BEST COPY AVAILABLE

HOWARD A. DOOLIN MIDDLE SCHOOL
MIAMI-DADE COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: New Middle School
FACILITY NAME & ADDRESS:
Howard A. Doolin Middle School
6401 S.W. 152 Avenue
Miami, FL 33193
(305) 386-6656
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade County Public Schools
Ivan M. Rodriquez
1450 N.E. 2 Avenue, Suite 569
Miami, FL 33132
(305) 995-4500
ARCHITECT, ADDRESS & PHONE NUMBER:
Charles H. Pawley Architect, P.A.
4515 Ponce De Leon Boulevard
Coral Gables, FL 33134
(305) 663-1600
CONTRACTOR, ADDRESS & PHONE NUMBER:
Shafer & Miller, Inc.
6855 S.W. 81 Street
Miami, FL 33143
(305) 667-8876
CONSTRUCTION CONTRACT DATE: November 1995
OCCUPANCY DATE: November 1997
SITE SIZE: 17 Acres
BUILDING AREA: 159,939 Sq. Ft.
GRADE LEVEL ORGANIZATION: 6 - 8
STUDENT CAPACITY: 1,320

TOTAL CONSTRUCTION COST: (includes site improve., site aquisition, furn & equip, & fees as applicable): $19,914,845
GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 22 Classrooms, 5 Resource Rooms, 7 Skills Labs, 7 Science Labs, 5 ESE Classrooms, 2 Art Labs, 3 Music Labs, 7 Vo-tech Labs, Gym, Administration, Library/Media, Auditorium, Stage, Dining, and Kitchen.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, softball field, basketball courts, covered play area, landscaping, and courtyards
FLOORS: Concrete slab on grade
ROOF: Built up roof
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Metal studs, gypsum board, and high impact one coat veneer.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl, ceramic tile, and quarry tile.
CEILINGS: 2x2 lay-in acoustical tile
HVAC: Cooling tower.
PLUMBING: Municipal water and sewer.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, emergency generator, computer networking, and energy management.



BEST COPY AVAILABLE

ENEIDA MASSAS HARTNER ELEMENTARY SCHOOL
MIAMI-DADE COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Eneida Massas Hartner Elementary School
401 N.W. 29 .Street
Miami, FL 33127
(305) 573-8181
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade County Public Schools
Ivan M. Rodriquez
1450 N.E. 2 Avenue, Suite 569
Miami, FL 33132
(305) 995-4500
ARCHITECT, ADDRESS & PHONE NUMBER:
Arquitectonica International Corporation
550 Brickell Avenue, Suite 200
Miami, FL 33131
(305) 372-1812
CONTRACTOR, ADDRESS & PHONE NUMBER:
Beauchamp Construction Co.
247 Minorca Avenue
Coral Gables, FL 33134
(305) 445-0819
CONSTRUCTION CONTRACT DATE: October 1995
OCCUPANCY DATE: November 1997
SITE SIZE: 5 Acres
BUILDING AREA: 104,686 Sq. Ft.
GRADE LEVEL ORGANIZATION: K - 5
STUDENT CAPACITY: 878

TOTAL CONSTRUCTION COST: (includes site improve., site aquisition, furn & equip, & fees as applicable): $13,516,172
GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 32 Classrooms, 8 Resource Rooms, 2 Skills Labs, 4 ESE Classrooms, Art, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, covered play area, basketball courts, landscaping, and courtyards
FLOORS: Concrete slab on grade. Second floor - poured concrete.
ROOF: Built up roof on precast concrete deck.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Metal studs with gypsum board.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl, ceramic tile, and quarry tile.
CEILINGS: 2x2 lay-in acoustical tile
HVAC: Air cooled chiller, cooling tower, and VAV boxes.
PLUMBING: Municipal water and sewer.
ELECTRICAL: Fluorescent and HID light fixtures. Telephone, CCTV, fire alarm, intercom, security, emergency generator, computer networking, and energy management.

ENEIDA MASSAS HARTNER ELEMENTARY SCHOOL
MIAMI-DADE COUNTY PUBLIC SCHOOLS



PRIMARY LEARNING CENTER A
MIAMI-DADE COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New Primary Learning Center
FACILITY NAME & ADDRESS:
Primary Learning Center A
8390 N.W. 7th Street
Miami, FL 33126
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade County Public Schools
Dr. Paul Phillips
1450 N.E. 2 Avenue
Miami, FL 33132-1308
(305) 995-4875
ARCHITECT, ADDRESS & PHONE NUMBER:
Gili - McGraw Architects
495 Biltmore Way, Suite 301
Coral Gables, FL 33134-5756
(305) 461-0900
CONTRACTOR, ADDRESS & PHONE NUMBER:
Church & Tower, Inc.
8600 NW 36th Street, 8th Floor
Miami, FL 33122
CONSTRUCTION CONTRACT DATE: October 1995
OCCUPANCY DATE: March 1997
SITE SIZE: 1.98 Acres
BUILDING AREA: 17,544 Sq. Ft.
GRADE LEVEL ORGANIZATION: K - 1
STUDENT CAPACITY: 250

TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $2,415,000
GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 10 Classrooms, 1 Resource Room, Administration, and Satellite Kitchen.
SPECIAL FEATURES or COMMENTS: Compact plan
SITE DEVELOPMENT: Asphalt drives and parking. Bus drop-off, play fields, and landscaping.
FLOORS: Concrete slab on grade.
ROOF: Steel joists, metal deck, light weight concrete, and membrane roofing.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Metal studs with gypsum board.
FLOOR FINISHES: Carpet, vinyl composition tile, quarry tile, and exposed concrete.
BASE: Vinyl
CEILINGS: 2x2 lay-in acoustical tile
HVAC: Heating and cooling by central electric chiller/ pump, VAV boxes with heat strips
PLUMBING: Municipal water and sewer. Copper water distribution pipes. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, and energy management.

PRIMARY LEARNING CENTER A
MIAMI-DADE COUNTY PUBLIC SCHOOLS



15

PRIMARY LEARNING CENTER B
MIAMI-DADE COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New Primary Learning Center
FACILITY NAME & ADDRESS:
Primary Learning Center B
9749 N.W. 127th Lane
Hialeah Gardens, FL 33016
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade County Public Schools
Dr. Paul Phillips
1450 N.E. 2 Avenue
Miami, FL 33132-1308
(305) 995-4875
ARCHITECT, ADDRESS & PHONE NUMBER:
Gili - McGraw Architects
495 Biltmore Way, Suite 301
Coral Gables, FL 33134-5756
(305) 461-0900
CONTRACTOR, ADDRESS & PHONE NUMBER:
Church & Tower, Inc.
8600 NW 36th Street, 8th Floor
Miami, FL 33122
CONSTRUCTION CONTRACT DATE: October 1995
OCCUPANCY DATE: March 1997
SITE SIZE: 1.18 Acres
BUILDING AREA: 17,452 Sq. Ft.
GRADE LEVEL ORGANIZATION: K - 1
STUDENT CAPACITY: 250

TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $2,415,000
GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 10 Classrooms, 1 Resource Room, Administration, and Satellite Kitchen,
SPECIAL FEATURES or COMMENTS: Compact plan
SITE DEVELOPMENT: Asphalt drives and parking. Bus drop-off, play fields, and landscaping.
FLOORS: Concrete slab on grade.
ROOF: Steel joists, metal deck, light weight concrete, and membrane roofing.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Metal studs with gypsum board.
FLOOR FINISHES: Carpet, quarry tile, and exposed concrete.
BASE: Vinyl
CEILINGS: 2x2 lay-in acoustical tile
HVAC: Heating and cooling by central electric chiller/ pump, VAV boxes with heat strips
PLUMBING: Municipal water and sewer. Copper water distribution pipes. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, and energy management.

PRIMARY LEARNING CENTER B
MIAMI-DADE COUNTY PUBLIC SCHOOLS



17

PRIMARY LEARNING CENTER C
MIAMI-DADE COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: New Primary Learning Center
FACILITY NAME & ADDRESS:
Primary Learning Center C
1575 N.W. 177th Street
North Miami Beach, FL 33162
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade County Public Schools
Dr. Paul Phillips
1450 N.E. 2 Avenue
Miami, FL 33132-1308
(305) 995-4875
ARCHITECT, ADDRESS & PHONE NUMBER:
Gili - McGraw Architects
495 Biltmore Way, Suite 301
Goral Gables, FL 33134-5756
(305) 461-0900
CONTRACTOR, ADDRESS & PHONE NUMBER:
Church & Tower, Inc.
8600 NW 36th Street, 8th Floor
Miami, FL 33122
CONSTRUCTION CONTRACT DATE: October 1995
OCCUPANCY DATE: March 1997
SITE SIZE: 1.23 Acres
BUILDING AREA: 17,404 Sq. Ft.
GRADE LEVEL ORGANIZATION: K - 1
STUDENT CAPACITY: 250

TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $2,415,000
GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 10 Classrooms, 1 Resource Room, Administration, and Satellite Kitchen,
SPECIAL FEATURES or COMMENTS: Compact plan
SITE DEVELOPMENT: Asphalt drives and parking. Bus drop-off, play fields, and landscaping.
FLOORS: Concrete slab on grade.
ROOF: Steel joists, metal deck, light weight concrete, and membrane roofing.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Metal studs with gypsum board.
FLOOR FINISHES: Carpet, quarry tile, and exposed concrete.
BASE: Vinyl
CEILINGS: 2x2 lay-in acoustical tile
HVAC: Heating and cooling by central electric chiller/ pump, VAV boxes with heat strips
PLUMBING: Municipal water and sewer. Copper water distribution pipes. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, and energy management.

PRIMARY LEARNING CENTER C
MIAMI-DADE COUNTY PUBLIC SCHOOLS



19

PRIMARY LEARNING CENTER D
MIAMI-DADE COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: New Primary Learning Center
FACILITY NAME & ADDRESS:
Primary Learning Center D
1025 N.W. 30th Avenue
Miami, FL 33125
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade County Public Schools
Dr. Paul Phillips
1450 N.E. 2 Avenue
Miami, FL 33132-1308
(305) 995-4875
ARCHITECT, ADDRESS & PHONE NUMBER:
Gili - McGraw Architects
495 Biltmore Way, Suite 301
Coral Gables, FL 33134-5756
(305) 461-0900
CONTRACTOR, ADDRESS & PHONE NUMBER:
Church & Tower, Inc.
8600 NW 36th Street, 8th Floor
Miami, FL 33122
CONSTRUCTION CONTRACT DATE: October 1995
OCCUPANCY DATE: March 1997
SITE SIZE: 1.65 Acres
BUILDING AREA: 17,405 Sq. Ft.
GRADE LEVEL ORGANIZATION: K - 1
STUDENT CAPACITY: 250

TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $2,415,000
GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 10 Classrooms, 1 Resource Room, Administration, and Satellite Kitchen.
SPECIAL FEATURES or COMMENTS: Compact plan
SITE DEVELOPMENT: Asphalt drives and parking. Bus drop-off and landscaping.
FLOORS: Concrete slab on grade.
ROOF: Steel joists, metal deck, light weight concrete, and membrane roofing.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Metal studs with gypsum board.
FLOOR FINISHES: Carpet, quarry tile, and exposed concrete.
BASE: Vinyl
CEILINGS: 2x2 lay-in acoustical tile
HVAC: Heating and cooling by central electric chiller/ pump, VAV boxes with heat strips
PLUMBING: Municipal water and sewer. Copper water distribution pipes. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, and energy management.

PRIMARY LEARNING CENTER D
MIAMI-DADE COUNTY PUBLIC SCHOOLS



LAURA C. SAUNDERS ELEMENTARY SCHOOL
MIAMI-DADE COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: Replacement Elementary School
FACILITY NAME & ADDRESS:
Laura C. Saunders Elementary School
505 S.W. 8th Street
Homestead, FL 33030
(305) 995-3933
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade County Public Schools
Dr. Paul Phillips
1450 N.E. 2 Avenue
Miami, FL 33132-1308
(305) 995-4875
ARCHITECT, ADDRESS & PHONE NUMBER:
Blitstein Design Associates
285 Sevilla Avenue
Coral Gables, FL 33134
(305) 444-4443
CONTRACTOR, ADDRESS & PHONE NUMBER:
Danville, Findorff, Inc.
2811 S. W. 70th Avenue
Miami, FL 33155
CONSTRUCTION CONTRACT DATE: April 1995
OCCUPANCY DATE: February 1997
SITE SIZE: 7.22 Acres
GRADE LEVEL ORGANIZATION: K-5
STUDENT CAPACITY: 1,079
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $12,154,000

GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 38 Classrooms, 6 Resource Rooms, 2 Skills Labs, 7 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: Buildings form a campus plan with covered walkway connections.
SITE DEVELOPMENT: Asphalt drives and parking. Bus drop-off, parent drop-off, play fields, basketball courts, covered play area, and landscaping.
FLOORS: Slab on grade. Second floor - reinforced poured concrete slabs.
ROOF: Steel joist, metal deck, light weight concrete and rigid insulation. Built-up roof.
EXTERIOR WALLS: Reinforced concrete masonry units, stucco finish.
INTERIOR WALLS: Metal studs with gypsum board and veneer plaster.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, wood, and exposed concrete.
BASE: Rubber, ceramic tile, and quarry tile.
CEILINGS: 2x2 drop-in acoustic tile. 2x2 mylar face tile. Painted cement plaster.
HVAC: Central electric chiller/pump, VAV boxes with heat strips.
PLUMBING: Municipal water and sewer. Copper water distribution pipes. PVC sewage drainage system.
ELECTRICAL: Fluorescent and HID light fixtures, telephone, CCTV, fire alarm, intercom, emergency generator, computer networking, and energy management.

LAURA C. SAUNDERS ELEMENTARY SCHOOL
MIAMI-DADE COUNTY PUBLIC SCHOOLS



EDWARD L. WHIGHAM ELEMENTARY SCHOOL
MIAMI-DADE COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Edward L. Whigham Elementary School
21545 S.W. 87th Avenue
Miami, FL 33189
(305) 234-4840
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade County Public Schools
Dr. Paul Phillips
1450 N.E. 2 Avenue
Miami, FL 33132-1308
(305) 995-4875
ARCHITECT, ADDRESS & PHONE NUMBER:
Robert Bradford Browne Architects
3310 Ponce de Leon Blvd., Suite 270
Coral Gables, FL 33134
(305) 445-1502
CONTRACTOR, ADDRESS & PHONE NUMBER:
MCM Corporation
1401 S. W. 1st Street #205
Miami, FL 33135
CONSTRUCTION CONTRACT DATE: September 1995
OCCUPANCY DATE: January 1997
SITE SIZE: 11.43 Acres
BUILDING AREA: 96,178 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 5
STUDENT CAPACITY: 919
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable):
$12,523,000

GENERAL DESCRIPTION OF FACILITY: A 2 story facility consisting of: 32 Classrooms, 6 Resource Rooms, 2 Skills Labs, 6 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: Courtyard plan with covered walkways.
SITE DEVELOPMENT: Asphalt drives and parking. Bus drop-off, play fields, and landscaping.
FLOORS: Concrete slab on grade. Second floor - reinforced poured concrete.
ROOF: Lightweight concrete over metal deck and steel joist. Membrane & metal roofing.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Metal studs with gypsum board, painted finish.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and exposed concrete.
BASE: Vinyl and ceramic tile.
CEILINGS: Suspended acoustical ceiling tile and exposed trusses.
HVAC: Heating and cooling by central electric chiller/pump, VAV boxes with heat strips.
PLUMBING: Copper water distribution pipes. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, and intercom.

EDWARD L. WHIGHAM ELEMENTARY SCHOOL
MIAMI-DADE COUNTY PUBLIC SCHOOLS



INDIAN TRAILS K-8 SCHOOL
FLAGLER COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New K - 8 School
FACILITY NAME & ADDRESS:
Indian Trails K-8 School
5505 N. Belle Terre Parkway
Palm Coast, FL 32137
(904) 446-6732
OWNER, CONTACT PERSON & PHONE NUMBER:
Flagler County Public Schools
Dr. Donn V. Kaupke
3039 Highway 60 East
Bunnell, FL 32110
(904) 437-7526
ARCHITECT, ADDRESS & PHONE NUMBER:
Gibraltar Design
9102 N. Meridian St., Suite 300
Indianapolis, IN 46260
(317) 580-5777
CONTRACTOR, ADDRESS & PHONE NUMBER:
Dimare
3545 US 1 South
St. Augustine, FL 32086
(904) 797-3328
CONSTRUCTION CONTRACT DATE: August 1994
OCCUPANCY DATE: August 1996
SITE SIZE: 86 Acres
BUILDING AREA: 225,000 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 8
STUDENT CAPACITY: 1,380
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $19,500,000
GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 45 Classrooms, 9 Resource Rooms, 4 Skills Labs, 4 Science Labs, 8 ESE Classrooms, 2 Art Labs, 2 Music Labs, Gym, Stage, Administration, Library/Media, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: The building meets both elementary and middle school educational space needs while sharing the common areas. A modular classroom layout is utilized that allows for functional and frugal school construction. Careful planning allows easy orientation for students moving throughout the building while respecting the separation between middle school and elementary school students.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, softball field, covered play area, basketball courts, tennis courts, landscaping, and courtyards.
FLOORS: Concrete slab on grade.
ROOF: Metal deck with rigid insulation. Modified bitumen membrane and metal roofing.
EXTERIOR WALLS: Concrete masonry units with brick and EIFIS.
INTERIOR WALLS: Painted concrete masonry units and metal studs with gypsum board.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, quarry tile, and wood.
BASE: Rubber, ceramic tile, and quarry tile.
CEILINGS: 2x4 lay-in acoustical tile, gypsum board, and exposed.
HVAC: Air cooled chiller, VAV boxes, and heat recovery.
PLUMBING: Municipal water and sewer. PVC sewage drainage system. Fire sprinkler system. LP gas.
ELECTRICAL: Fluorescent and HID light fixtures. Telephone, CCTV, fire alarm, intercom, emergency generator, and computer networking.

INDIAN TRAILS K-8 SCHOOL
FLAGLER COUNTY PUBLIC SCHOOLS



27

BELL ELEMENTARY SCHOOL
GILCHRIST COUNTY SCHOOL DISTRICT



TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Bell Elementary School
Highway 129 South
Bell, FL 32619
(352) 463-3275
OWNER, CONTACT PERSON & PHONE NUMBER:
Gilchrist County School Board
Don Thomas, Superintendent
Post Office Drawer 67
Trenton, FL 32693
(352) 463-3200
ARCHITECT, ADDRESS & PHONE NUMBER:
JRA Architects, Inc.
2551 Blairstone Pines Drive
Tallahassee, FL 32301
(850) 878-7891
CONTRACTOR, ADDRESS & PHONE NUMBER:
M. M. Parrish Construction Company
3455 SW 42nd Avenue
Gainesville, FL 32608
(352) 378-1571
CONSTRUCTION CONTRACT DATE: August 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 37 Acres
BUILDING AREA: 92,000 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 5
STUDENT CAPACITY: 606
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $11,700,000

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 22 Classrooms, 4 Resource Rooms, 2 Skills Labs, 3 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: The new facility was built adjacent to an existing K-12 campus. Play fields are shared with the original school. Project included new outdoor basketball and tennis courts, new cafetorium and outdoor amphitheater for both school and community use.
SITE DEVELOPMENT: Asphalt and concrete drives and parking. Bus drop-off, play fields, baseball field, tennis courts, covered play area, basketball courts, and landscaping.
FLOORS: Concrete slab on grade.
ROOF: Standing seam metal roof
EXTERIOR WALLS: Concrete masonry units and brick.
INTERIOR WALLS: Concrete masonry units and gypsum board.
FLOOR FINISHES: Carpet, vinyl composition tile, and ceramic tile.
BASE: Vinyl, ceramic tile, and quarry tile.
CEILINGS: 2x2 lay-in acoustical tile and gypsum board
HVAC: Air cooled chiller.
PLUMBING: Private water supply and treatment plant.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, emergency generator, fiber optics, and computer networking.

BELL ELEMENTARY SCHOOL
GILCHRIST COUNTY SCHOOL DISTRICT



29

CLEWISTON MIDDLE SCHOOL
HENDRY COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New Middle School
FACILITY NAME & ADDRESS:
Clewiston Middle School
601 W. Pasadena Avenue
Clewiston, FL 33440
(941) 983-1530
OWNER, CONTACT PERSON & PHONE NUMBER:
Hendry County Public Schools
Ed Upthegrove
475 W. Osceola Avenue
Clewiston, FL 33440
(941) 902-4244
ARCHITECT, ADDRESS & PHONE NUMBER:
Richard G. Allen, Architects
2364 Fruitville Road
Sarasota, FL 34237
(941) 957-0030
CONTRACTOR, ADDRESS & PHONE NUMBER:
Brown & Root Building Company
5830 142nd Avenue, North
Clearwater, FL 33760
(813) 539-7668
CONSTRUCTION CONTRACT DATE: February 1996
OCCUPANCY DATE: August 1998
SITE SIZE: 34 Acres
BUILDING AREA: 150,000 Sq. Ft.
GRADE LEVEL ORGANIZATION: 6 - 8
STUDENT CAPACITY: 1,127
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $18,570,768

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 14 Classrooms, 6 Resource Rooms, 4 Skills Labs, 7 Science Labs, 8 ESE Classrooms, 2 Art Labs., 3 Music Labs., 7 Vo-tech Labs, Gym, Administration, Library/Media, Auditorium, Stage, Cafetorium, Kitchen, and Multi-purpose Room.
SPECIAL FEATURES or COMMENTS: The school is equipped with latest Sprint (TekNet) Communication System and Data Retrieval System
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, softball field, basketball courts, tennis courts, landscaping, and courtyards.
FLOORS: Concrete slab on grade.
ROOF: Metal roof deck and roofing.
EXTERIOR WALLS: Concrete masonry units with brick and EIFIS.
INTERIOR WALLS: Concrete masonry units and metal studs with gypsum board and fiberbond gypsum.
FLOOR FINISHES: Carpet, vinyl composition tile, and ceramic tile. Stage and gym - wood.
BASE: Vinyl and ceramic tile.
CEILINGS: 2x4 lay-in acoustical tile, gypsum board and plaster.
HVAC: Water cooled chiller, cooling tower, heat strips, chilled water system, heat pump, VAV and CV boxes.
PLUMBING: Municipal water and sewer. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, fiber optics, computer networking, and energy management.



BEST COPY AVAILABLE

HILL-GUSTAT MIDDLE SCHOOL
HIGHLANDS COUNTY SCHOOLS



TYPE OF FACILITY: New Middle School
FACILITY NAME & ADDRESS:
Hill-Gustat Middle School
4700 Schumaker Road
Sebring, FL 33872
(941) 314-5240
OWNER, CONTACT PERSON & PHONE NUMBER:
Highlands County Schools
426 Schools Street
Sebring, FL 33870
(941) 471-5602
ARCHITECT, ADDRESS & PHONE NUMBER:
Strollo Architects Inc.
68 South Ivanhoe Boulevard
Orlando, FL 32804
(407) 423-5355
CONTRACTOR, ADDRESS & PHONE NUMBER:
A. D. Arnold Construction Co.
2929 Wadsworth Avenue
Orlando, FL 32806
(407) 422-8444
CONSTRUCTION CONTRACT DATE: April 1995
OCCUPANCY DATE: 1996
SITE SIZE: 40 Acres
BUILDING AREA: 107,000 Sq. Ft.
GRADE LEVEL ORGANIZATION: 6 - 8
STUDENT CAPACITY: 899 Core / 552 Current
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $6,000,000.00

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 9 Classrooms, 3 Resource Rooms, 3 Science Labs, 5 ESE Classrooms, Art, 2 Music Labs, 3 Vo-tech Labs, Gym, Stage, Multipurpose Room, Library/Media, Administration, Dining, and Kitchen.
SPECIAL FEATURES or COMMENTS: The school was designed as an open campus plan with self contained 6th, 7th, and 8th grade learning centers. The facility includes a full court Gymnatorium with bleachers and a Performing Arts Center with an elevated stage. This facility supports the educational, recreational and cultural demands of the community.
SITE DEVELOPMENT: Clearing and grading. Storm water system.
FLOORS: Concrete slab on grade
ROOF: Standing seam metal roof.
EXTERIOR WALLS: Metal building panels and painted concrete masonry units.
INTERIOR WALLS: Painted concrete masonry units and drywall.
FLOOR FINISHES: Carpet, vinyl composition tile, and sheet vinyl.
BASE: Vinyl
CEILINGS: Lay-in acoustical tile and painted drywall and plaster.
HVAC: Air cooled chillers for CW and electric heat.
PLUMBING: PVC and copper.
ELECTRICAL: Campus transformer and distribution system. Integrated data and telephone system.

HILL-GUSTAT MIDDLE SCHOOL
HIGHLANDS COUNTY SCHOOLS



GORDON BURNETT MIDDLE SCHOOL
HILLSBOROUGH COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New Middle School
FACILITY NAME & ADDRESS:
Gordon Burnett Middle School
1010 Kingsway Road North
Seffner, FL 33584
(813) 744-6745
OWNER, CONTACT PERSON & PHONE NUMBER:
Hillsborough County Public Schools
Mr. J. Thomas Blackwell
901 East Kennedy Boulevard
Tampa, FL 33601
(813) 272-4112
ARCHITECT, ADDRESS & PHONE NUMBER:
Holmes Hepner & Associates Architects
100 West Kennedy Boulevard, Suite 300
Tampa, FL 33602
(813) 229-0614
CONTRACTOR, ADDRESS & PHONE NUMBER:
G. H. Johnson Construction Company
5300 West Cypress Street, Suite 261
Tampa, FL 33607
(813) 289-5505
CONSTRUCTION CONTRACT DATE: October 1994
OCCUPANCY DATE: August 1996
SITE SIZE: 27.85 Acres
BUILDING AREA: 158,077 Sq. Ft.
GRADE LEVEL ORGANIZATION: 6 - 8
STUDENT CAPACITY: 1,123
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable):
$18,712,118.00

GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 18 Classrooms, 2 Skills Labs, 4 Resource Rooms, 11 Science Labs, Art, 4 Music Labs, 8 ESE Classrooms, 5 Vo-tech Labs, Gym, Administration, Library/Media, Dining, Kitchen, and a Multipurpose Room with Stage.
SPECIAL FEATURES or COMMENTS: House concept for different grade levels is utilized. A large public courtyard is located by the gym and food service.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, softball field, basketball courts, tennis courts, landscaping, and courtyards.
FLOORS: Concrete slab on grade
ROOF: Metal deck with rigid insulation. Built-up roof.
EXTERIOR WALLS: Brick
INTERIOR WALLS: Metal studs and gypsum board.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Rubber
CEILINGS: 2x4 lay-in acoustical tile
HVAC: Water cooled chiller, chilled water system, VAV boxes, and heat recovery.
PLUMBING: Municipal water supply and sewer. Cast iron sewage drainage system. LP Gas
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, emergency generator, fiber optics, computer networking, and energy management.

GORDON BURNETT MIDDLE SCHOOL
HILLSBOROUGH COUNTY PUBLIC SCHOOLS



35

WALTER L. SICKLES HIGH SCHOOL
HILLSBOROUGH COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New High School
FACILITY NAME & ADDRESS:
Walter L. Sickles High School
7950 Gunn Highway
Tampa, FL 33626
(813) 631-4742
OWNER, CONTACT PERSON & PHONE NUMBER:
Hillsborough County Public Schools
Mr. J. Thomas Blackwell
901 East Kennedy Boulevard
Tampa, FL 33601
(813) 272-4112
ARCHITECT, ADDRESS & PHONE NUMBER:
Ranon & Partners, Inc., Architects
515 West Bay Street, Suite 200
Tampa, FL 33606-2796
(813) 253-3465
CONTRACTOR, ADDRESS & PHONE NUMBER:
Walbridge Aldinger
410 Ware Blvd., #900
Tampa, FL 33619-4439
(813) 622-8900
CONSTRUCTION CONTRACT DATE: June 1995
OCCUPANCY DATE: August 1997
SITE SIZE: 84 Acres
BUILDING AREA: 307,100 Sq. Ft.
GRADE LEVEL ORGANIZATION: 9-12
STUDENT CAPACITY: 2,177
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $36,516,527.42
GENERAL DESCRIPTION OF FACILITY: A 2 story facility consisting of: 35 Classrooms, 5 Resource Rooms, 21 Skills Labs, 9 Science Labs, 12 ESE Classrooms, 2 Art Labs, 4 Music Labs, 11 Vo-tech Labs, Gym, Administration, Library/Media, Auditorium, Stage, Dining, and Kitchen.
SPECIAL FEATURES or COMMENTS: The campus consists of eight structures which form a central open-air mall which is the campus's heart. Each classroom/laboratory building has a flexible, adaptable chassis made from economical, repetitive construction systems.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, softball field, basketball courts, tennis courts, football field, running track, landscaping, and courtyards.
FLOORS: Concrete slab on grade. Second floor - concrete topping over precast hollow core slabs.
ROOF: Metal deck, rigid insulation and built-up roof.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Concrete masonry units, and metal studs with metal lath and cement plaster.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl, ceramic tile, and quarry tile.
CEILINGS: 2x2 lay-in acoustical tile
HVAC: Water cooled chiller, water tower, chilled water system, and VAV boxes.
PLUMBING: Municipal water and sewer. Copper water distribution pipes. PVC sewage drainage system. Fire sprinkler system at stage. LP-gas.
ELECTRICAL: Flourescent light fixtures, telephone, CCTV, fire alarm, intercom, security, emergency generator, fiber optics, computer networking, and energy management.

WALTER L. SICKLES HIGH SCHOOL
HILLSBOROUGH COUNTY PUBLIC SCHOOLS



37

WILLIAMS MIDDLE SCHOOL
HILLSBOROUGH COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: New Middle School
FACILITY NAME & ADDRESS:
Williams Middle Schools
5020 North 47th Street
Tampa, FL 33610
(813) 744-8600
OWNER, CONTACT PERSON & PHONE NUMBER:
Hillsborough County Public Schools
Mr. J. Thomas Blackwell
901 East Kennedy Boulevard
Tampa, FL 33601
(813) 272-4112
ARCHITECT, ADDRESS & PHONE NUMBER:
Holmes Hepner & Associates Architects
100 West Kennedy Boulevard, Suite 300
Tampa, FL 33602
(813) 229-0614
CONTRACTOR, ADDRESS & PHONE NUMBER:
Greater Bay Construction Company
5215 West Laurel Street, Suite 106
Tampa, FL 33607
(813) 282-0709
CONSTRUCTION CONTRACT DATE: June 1995
OCCUPANCY DATE: January 1997
SITE SIZE: 11.96 Acres
BUILDING AREA: 139,368 Sq. Ft.
GRADE LEVEL ORGANIZATION: 6-8
STUDENT CAPACITY: 1,013
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $13,934,195.00

GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 17 Classrooms, 5 Resource Rooms, 3 Skills Labs, 8 Science Labs, 5 ESE Classrooms, Art, 2 Music Labs, Gym, Administration, Library/Media, Dining, Kitchen, and a Multipurpose Room with Stage.
SPECIAL FEATURES or COMMENTS: A house concept for different grade levels is utilized.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, softball field, basketball courts, tennis courts, landscaping, and courtyards.
FLOORS: Concrete slab on grade.
ROOF: Metal roof deck with rigid insulation. Built-up roofing.
EXTERIOR WALLS: Concrete masonry units with brick.
INTERIOR WALLS: Metal studs, gypsum board and veneer plaster
FLOOR FINISHES: Carpet, vinyl composition tile, and ceramic tile.
BASE: Rubber
CEILINGS: 2x4 lay-in acoustical tile
HVAC: Water cooled chiller, chilled water system, VAV boxes, and heat recovery.
PLUMBING: Municipal water and sewer. Cast iron sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, and emergency generator, fiber optics, computer networking, and energy management.


ADMIN
GYM
CLRMS
CLRMS
CLASSROOMS
ESE
DINING
MUSIC
VO-TECH
CLRMS
KIT
ESE
ESE
MECH
MULTI-
PURPOSE
STAGE

39

CARLOS E. HAILE MIDDLE SCHOOL
MANATEE COUNTY SCHOOL BOARD

TYPE OF FACILITY: New Middle School
FACILITY NAME & ADDRESS:
Carlos E. Haile Middle School
9501 State Road 64 East
Bradenton, FL 34202
(941) 714-7240
OWNER, CONTACT PERSON & PHONE NUMBER:
Manatee County School Board
William Horton, Facilities Department
2802-A 27th Street, East
Bradenton, FL 34208
(941) 741-7781
ARCHITECT, ADDRESS & PHONE NUMBER:
Schwab Twitty & Hanser, Inc.
515 North Flagler Drive, Suite 1400
West Palm Beach, FL 33401
(561) 832-5599
CONTRACTOR, ADDRESS & PHONE NUMBER:
Morganti Florida, Inc.
1800 Australian Ave., S., Suite 302
West Palm Beach, FL 33409
(561) 689-0200
CONSTRUCTION CONTRACT DATE: June 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 27.6 Acres
BUILDING AREA: 151,127 Sq. Ft.
GRADE LEVEL ORGANIZATION: 6 - 8
STUDENT CAPACITY: 1,185
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable):
$13,712,486

GENERAL DESCRIPTION OF FACILITY: A one and two story facility consisting of: 3 Resource Rooms, 22 Skills Labs, 5 Science Labs, 3 ESE Classrooms, Art, 7 Music Labs, 5 Vo-tech Labs, Administration, Library/Media, Gym, Stage, Cafetorium, and Kitchen.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, softball field, basketball courts, tennis courts, landscaping, and courtyards.
FLOORS: Concrete slab on grade.
ROOF: Single ply roofing on metal deck and light weight concrete.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Concrete masonry units and metal studs, gypsum board and veneer plaster.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, quarry tile, epoxy, and wood.
BASE: Vinyl, ceramic tile, quarry tile, and epoxy.
CEILINGS: 2x2 and 2x4 lay-in acoustical tile, plaster, gypsum board, and exposed.
HVAC: Water cooled chiller, chilled water system with VAV boxes.
PLUMBING: Municipal water and sewer service, lift station. Natural gas.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, intercom, security, emergency generator, and computer networking.


VO-TECH
VO-TECH
KIT
ART
MUSIC
DINING
VO-TECH
STAGE
SKILLS
VO-TECH
CLRMS
CLASSROOMS
ADMINISTRATION
GYM
CLASSROOMS
MEDIA
GREEN
HOUSE

GREENWAY ELEMENTARY - SOUTHEAST ELEMENTARY SCHOOL "K"
MARION COUNTY SCHOOL DISTRICT

TYPE OF FACILITY: Replacement Elementary School
FACILITY NAME & ADDRESS:
Greenway Elementary School
207 Midway Road
Ocala, FL 34472
(352) 687-3322
OWNER, CONTACT PERSON & PHONE NUMBER:
Marion County School District
Dr. John D. Smith, Superintendent
512 SE Third Street
Ocala, FL 34478
(352) 620-7702
ARCHITECT, ADDRESS & PHONE NUMBER:
BRPH Architects-Engineers, Inc.
3275 Suntree Blvd.
Melbourne, FL 32940
(407) 254-7666
CONTRACTOR, ADDRESS & PHONE NUMBER:
DiMare Construction Co.
8345 US 1 South
St. Augustine, FL 32086
(904) 797-3328
CONSTRUCTION CONTRACT DATE: January 1996
OCCUPANCY DATE: January 1997
SITE SIZE: 15.8 Acres
BUILDING AREA: 85,973 Sq. Ft.
GRADE LEVEL ORGANIZATION: K - 5
STUDENT CAPACITY: 712
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $6,468,000

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 25 Classrooms, 8 Resource Rooms, 2 Skills Labs, 5 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: Facility is a compact campus design with interconnecting classrooms and teacher planning areas in each building. Easily accessible mechanical mezzanines are located above the core areas.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, softball field, covered play area, basketball courts, landscaping, and courtyards.
FLOORS: Concrete slab on grade
ROOF: Metal roof on pre-engineered building system
EXTERIOR WALLS: Concrete masonry units with brick.
INTERIOR WALLS: Painted concrete masonry units.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl, ceramic tile, and quarry tile.
CEILINGS: 2x2 lay-in acoustical tile and gypsum board.
HVAC: Water cooled chiller, cooling tower, and heat pump.
PLUMBING: Municipal water and sewer. PVC and cast iron sewage drainage system. LP gas.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, fiber optics, computer networking, and energy management.


SERVICE YARD
KIT
DINING
STAGE
INTERMEDIATE
INTERMEDIATE
ESE
ESE
PRIMARY
PRIMARY
RES.
MUSIC
RES.
COURT YARD
ART
MEDIA
ADMIN
INTERMEDIATE
INTERMEDIATE
ESE
ESE
KINDERGARTEN
KINDERGARTEN

43

ANTIOCH ELEMENTARY SCHOOL
OKALOOSA COUNTY SCHOOL DISTRICT



TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Antioch Elementary School
4700 Whitehurst Lane
Crestview, FL 32536
(850) 683-7540
OWNER, CONTACT PERSON & PHONE NUMBER:
Okaloosa County School District
William Smith
120 Lowery Place
Fort Walton Beach, FL 32548
(850) 833-3100
ARCHITECT, ADDRESS & PHONE NUMBER:
Amspacher-Amspacher Architects
2003 N. Ninth Avenue
Pensacola, FL 32503
(850) 434-0123
CONTRACTOR, ADDRESS & PHONE NUMBER:
Lord & Son Construction Co
P. O. Box 1808
Fort Walton Beach, FL 32549
(850) 863-5158
CONSTRUCTION CONTRACT DATE: May 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 20 Acres
BUILDING AREA: 76,000 Sq. Ft.

GRADE LEVEL ORGANIZATION: K -5
STUDENT CAPACITY: 800
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $5,727,009.21
GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 24 Classrooms, 2 Resource Rooms, 1 Skills Lab, 1 Science Lab, 4 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, basketball courts, and landscaping.
FLOORS: Concrete slab on grade
ROOF: Metal deck with rigid insulation and metal roofing.
EXTERIOR WALLS: Concrete masonry units with brick.
INTERIOR WALLS: Concrete masonry units.
FLOOR FINISHES: Carpet and vinyl composition tile.
BASE: Vinyl
CEILINGS: 2x4 lay-in acoustical tile
HVAC: VAV boxes
PLUMBING: Municipal water and sewer. PVC sewage drainage system.
ELECTRICAL: Flourescent light fixtures, telephone, CCTV, fire alarm, intercom, and computer networking.

ANTIOCH ELEMENTARY SCHOOL
OKALOOSA COUNTY SCHOOL DISTRICT



DAVIDSON MIDDLE SCHOOL
OKALOOSA COUNTY SCHOOL DISTRICT

TYPE OF FACILITY: New Middle - Vocational Center
FACILITY NAME & ADDRESS:
Davidson Middle School
6261 Old Bethel Road
Crestview, FL 32536
(850) 683-7500
OWNER, CONTACT PERSON & PHONE NUMBER:
Okaloosa County School District
William Smith
120 Lowery Place
Fort Walton Beach, FL 32548
(850) 833-3100
ARCHITECT, ADDRESS & PHONE NUMBER:
Bay Design Associates
102 East Garden Street
Pensacola, FL 32501
(850) 432-0706
CONTRACTOR, ADDRESS & PHONE NUMBER:
Ajax Building Corp
251 E. Harrison Street
Tallahassee, FL 32301
(850) 224-9571
CONSTRUCTION CONTRACT DATE: May 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 30 Acres
BUILDING AREA: 130,000 Sq. Ft.
GRADE LEVEL ORGANIZATION: 6 - 8

STUDENT CAPACITY: 1,200
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $9,431,502.34
GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 27 Classrooms, 4 Resource Rooms, 5 Skills Labs, 3 Science Labs, 7 ESE Classrooms, Art, 2 Music Labs, Gym, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, softball field, basketball courts, tennis courts, football field, and landscaping.
FLOORS: Concrete slab on grade
ROOF: Metal deck and roofing with rigid insulation
EXTERIOR WALLS: Concrete masonry units with brick and EIFIS
INTERIOR WALLS: Concrete masonry units with veneer plaster.
FLOOR FINISHES: Carpet and vinyl composition tile.
BASE: Vinyl
CEILINGS: 2x4 lay-in acoustical tile
HVAC: VAV boxes
PLUMBING: Municipal water and sewer. PVC sewage drainage system. Natural gas.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, and computer networking.

46


MAIN ENTRANCE
ADMIN
MEDIA
SERVICE YARD
KIT
DINING
STAGE
MUSIC
GYM
SIXTH GRADE WING
SEVENTH GRADE WING
EIGHTH GRADE WING
ATHLETIC WING

DESTIN MIDDLE SCHOOL @ REGATTA BAY
OKALOOSA COUNTY SCHOOL DISTRICT



TYPE OF FACILITY: New Middle School
FACILITY NAME & ADDRESS:
Destin Middle School @ Regatta Bay
400 Danny Wuerffel Way
Destin, FL 32541
(850) 833-7655
OWNER, CONTACT PERSON & PHONE NUMBER:
Okaloosa County School District
William Smith
120 Lowery Place
Fort Walton Beach, FL 32548
(850) 833-3100
ARCHITECT, ADDRESS & PHONE NUMBER:
DAG Architects
P. O. Box 1395
Destin, FL 32544
(850) 837-8152
CONTRACTOR, ADDRESS & PHONE NUMBER:
Whitesell Greene, Inc.
4520 North Davis Highway
Pensacola, FL 32503
(850) 434-5311
CONSTRUCTION CONTRACT DATE: May 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 20 Acres
BUILDING AREA: 86,000 Sq. Ft.

GRADE LEVEL ORGANIZATION: 6 - 8
STUDENT CAPACITY: 850
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $8,039,825.65
GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 15 Classrooms, 2 Resource Rooms, 5 Skills Labs, Science Lab, 2 ESE Classrooms, Art, 2 Music Labs, Gym, Administration, Library/ Media, Stage, Cafetorium, and Kitchen.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, baseball field, softball field, basketball courts, landscaping, football field, and track.
FLOORS: Concrete slab on grade.
ROOF: Metal deck, rigid insulation, and metal roofing.
EXTERIOR WALLS: Concrete masonry units and brick.
INTERIOR WALLS: Concrete masonry units.
FLOOR FINISHES: Carpet and vinyl composition tile.
BASE: Vinyl
CEILINGS: 2x4 lay-in acoustical tile
HVAC: VAV boxes
PLUMBING: Municipal water and sewer. PVC sewage drainage system. Natural gas.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, and computer networking.


MAIN
ENTRANCE
ADMIN
MEDIA
ACADEMIC WING
GYM
ACADEMIC WING
MUSIC
DINING
KIT

49

DISCOVERY MIDDLE SCHOOL
ORANGE COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New Middle School
FACILITY NAME & ADDRESS:
Discovery Middle School
601 Woodbury Road
Orlando, FL 32828
(307) 384-1555
OWNER, CONTACT PERSON & PHONE NUMBER:
Orange County Public Schools
Terry Adsit
6501 Magic Way, Building 100-A
Orlando, FL 32809
(407) 317-3700, Ext. 5212
ARCHITECT, ADDRESS & PHONE NUMBER:
Schenkel & Shultz
200 E. Robinson St., Suite 300
Orlando, FL 32801
(407) 872-3322
CONTRACTOR, ADDRESS & PHONE NUMBER:
Centex Rooney
9025 Boggy Creek Road, Unit 2
Orlando, FL 32824
(407) 856-7619
CONSTRUCTION CONTRACT DATE: December 1994
OCCUPANCY DATE: March 1996
SITE SIZE: 30 Acres
BUILDING AREA: 158,711 Sq. Ft.
GRADE LEVEL ORGANIZATION: 6 - 8
STUDENT CAPACITY: 1,275
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $18,800,000.00

GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 25 Classrooms, 4 Resource Rooms, 5 Skills Labs, 7 Science Labs, Art, 2 Music Labs, 5 ESE Classrooms, 2 Vo-tech Labs, Gym, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: "Educational Village" with buildings surrounding a "Town Square". Classrooms have a secure arrangement.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, softball field, basketball courts, tennis courts, landscaping, and courtyards.
FLOORS: Concrete slab on grade. Second floor - reinforced poured concrete.
ROOF: Metal deck with shingle roof.
EXTERIOR WALLS: Concrete masonry units with brick.
INTERIOR WALLS: Painted concrete masonry units.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, quarry tile, and wood.
BASE: Vinyl, rubber, ceramic tile, and quarry tile.
CEILINGS: 2x2 lay-in acoustical tile, plaster, gypsum board, and exposed.
HVAC: Air cooled chiller, chilled water system, VAV boxes.
PLUMBING: Cast iron sewage drainage system. Natural gas.
ELECTRICAL: Fluorescent and HID light. Direct and indirect lighting. Telephone, CCTV, fire alarm, intercom, security, emergency generator, computer networking, and energy management.


VO-TECH
MUSIC
ART
MEDIA
GYM
FOOD SERVICE
CLASSROOMS
CLASSROOMS
ADMIN
MAIN ENTRANCE

LAKE WHITNEY ELEMENTARY SCHOOL "R"
ORANGE COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Lake Whitney Elementary School
1351 Windermere Road
Windermere, FL 34786
(407) 877-8888
OWNER, CONTACT PERSON & PHONE NUMBER:
Orange County Public Schools
Terry Adsit
6501 Magic Way, Building 100-A
Orlando, FL 32809
(407) 317-3700, Ext. 5212
ARCHITECT, ADDRESS & PHONE NUMBER:
BRPH Architects-Engineers
3275 Suntree Boulevard
Melbourne, FL 32940
(407) 254-7666
CONTRACTOR, ADDRESS & PHONE NUMBER:
Heery/Sverdrup Joint Venture
6501 Magic Way, Building 100-A
Orlando, FL 32803
(407) 317-3700, Ext. 5320
CONSTRUCTION CONTRACT DATE: October 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 15 Acres
BUILDING AREA: 106,851 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 5
STUDENT CAPACITY: 1,106
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable):
$12,000,000

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 30 Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: The facility is a compact campus design with interconnecting classrooms and interconnecting teacher planning areas in each building. Easily accessible mechanical mezzanines are provided above the core areas.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, softball field, covered play area, landscaping, and courtyard.
FLOORS: Concrete slab on grade
ROOF: Metal roof on pre-engineered building system.
EXTERIOR WALLS: Concrete masonry units and brick.
INTERIOR WALLS: Concrete masonry units.
FLOOR FINISHES: Carpet, vinyl composition tile, and quarry tile.
BASE: Vinyl and quarry tile.
CEILINGS: 2x2 and 2x4 lay-in acoustical tile and gypsum board.
HVAC: Heat pumps
PLUMBING: Municipal water and sewer. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, fiber optics, and computer networking.

LAKE WHITNEY ELEMENTARY SCHOOL "R"
ORANGE COUNTY PUBLIC SCHOOLS



53

ROSEMONT ELEMENTARY SCHOOL "T"
ORANGE COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Rosemont Elementary School
4650 Point Look Out Road
Orlando, FL 32808
(407) 522-6050
OWNER, CONTACT PERSON & PHONE NUMBER:
Orange County Public Schools
Terry Adsit
6501 Magic Way, Building 100-A
Orlando, FL 32809
(407) 317-3700, Ext. 5212
ARCHITECT, ADDRESS & PHONE NUMBER:
BRPH Architects-Engineers
3275 Suntree Boulevard
Melbourne, FL 32940
(407) 254-7666
CONTRACTOR, ADDRESS & PHONE NUMBER:
Heery/Sverdrup Joint Venture
6501 Magic Way, Building 100-A
Orlando, FL 32803
(407) 317-3700, Ext. 5320
CONSTRUCTION CONTRACT DATE: October 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 15 Acres
BUILDING AREA: 106,851 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 5
STUDENT CAPACITY: 1,106
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable):
$11,400,000

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 30 Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: The facility is a compact campus design with interconnecting classrooms and interconnecting teacher planning areas in each building. Easily accessible mechanical mezzanines are provided above the core areas.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, softball field, covered play area, landscaping, and courtyards.
FLOORS: Concrete slab on grade
ROOF: Metal roof on pre-engineered building system.
EXTERIOR WALLS: Concrete masonry units and brick.
INTERIOR WALLS: Concrete masonry units.
FLOOR FINISHES: Carpet, vinyl composition tile, and quarry tile,
BASE: Vinyl and quarry tile
CEILINGS: 2x2 and 2x4 lay-in acoustical tile and gypsum board.
HVAC: Heat pumps
PLUMBING: Municipal water and sewer. PVC sewage disposal system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, fiber optics, and computer networking.


SERVICE YARD
KIT
DINING
STAGE
COURT YARD
MEDIA
ADMIN
MAIN ENTRANCE
INTERMEDIATE
RES.
INTERMEDIATE
RES.
SK
INT.
RES
INT.
PRIMARY
PRIMARY
ESE
ESE
MUSIC
ART
PRIMARY
PRIMARY
KINDERGARTEN
KINDERGARTEN
PK
PK

55

SOUTHWOOD ELEMENTARY SCHOOL "S"
ORANGE COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Southwood Elementary School
12600 Bisted Drive
Orlando, FL 32824
(407) 858-2230
OWNER, CONTACT PERSON & PHONE NUMBER:
Orange County Public Schools
Terry Adsit
6501 Magic Way, Building 100-A
Orlando, FL 32809
(407) 317-3700, Ext. 5212
ARCHITECT, ADDRESS & PHONE NUMBER:
BRPH Architects-Engineers
3275 Suntree Boulevard
Melbourne, FL 32940
(407) 254-7666
CONTRACTOR, ADDRESS & PHONE NUMBER:
Heery/Sverdrup Joint Venture
6501 Magic Way, Building 100-A
Orlando, FL 32803
(407) 317-3700, Ext. 5320
CONSTRUCTION CONTRACT DATE: October 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 15 Acres
BUILDING AREA: 106,851 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 5
STUDENT CAPACITY: 1,106
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $11,750,000

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 30 Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: The facility is a compact campus design with interconnecting classrooms and interconnecting teacher planning areas in each building. Easily accessible mechanical mezzanines are provided above the core areas.
SITE DEVELOPMENT: Asphalt drives, parking, parent drop-off, and bus drop-off. Play fields, baseball field, softball field, covered play area, landscaping, and courtyards.
FLOORS: Concrete slab on grade.
ROOF: Metal roof on pre-engineered building system.
EXTERIOR WALLS: Concrete masonry units and brick.
INTERIOR WALLS: Concrete masonry units.
FLOOR FINISHES: Carpet, vinyl composition tile, and quarry tile.
BASE: Vinyl and quarry tile.
CEILINGS: 2x2 and 2x4 lay-in acoustical tile, and gypsum board.
HVAC: Heat pumps
PLUMBING: Municipal water and sewer. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, fiber optics, and computer networking.

56

SOUTHWOOD ELEMENTARY SCHOOL "S"
ORANGE COUNTY PUBLIC SCHOOLS



57

SUNRISE ELEMENTARY SCHOOL
ORANGE COUNTY SCHOOL DISTRICT

TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Sunrise Elementary School
101 Lone Palm Road
Orlando, FL 32828
(407) 384-1585
OWNER, CONTACT PERSON & PHONE NUMBER:
Orange County School District
Terry Asdit
6501 Magic Way, Building 100-A
Orlando, FL 32809
(407) 317-3700, Ext. 5212
ARCHITECT, ADDRESS & PHONE NUMBER:
BRPH Architects-Engineers
3275 Suntree Blvd
Melbourne, FL 32940
(407)254-7666
CONTRACTOR, ADDRESS & PHONE NUMBER:
Ruby Buildings, Inc.
3939 Silver Star Road
Orlando, FL 32940
(407) 293-8217
CONSTRUCTION CONTRACT DATE: October 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 17.6 Acres
BUILDING AREA: 106.851 Sq. Ft.
GRADE LEVEL ORGANIZATION: K - 5
STUDENT CAPACITY: 1,106
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $9,375,205

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 30 Classrooms, 8 Resource Rooms, 1 Skills Lab, 5 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: The facility is a compact campus design with interconnecting classrooms and interconnecting teacher planning areas in each building. Easily accessible mechanical mezzanines are provided above the core areas.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, softball field, covered play area, basketball courts, landscaping, and courtyards.
FLOORS: Concrete slab on grade.
ROOF: Metal roof on pre-engineered building system.
EXTERIOR WALLS: Concrete masonry units
INTERIOR WALLS: Painted concrete masonry units.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl, ceramic tile, and quarry tile.
CEILINGS: 2x2 lay-in acoustical tile and gypsum board.
HVAC: Water cooled chiller, cooling tower, and heat pump.
PLUMBING: Municipal water and sewer. PVC and cast iron sewage drainage system. Natural gas
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, fiber optics, computer networking, and energy management.

SUNRISE ELEMENTARY SCHOOL
ORANGE COUNTY SCHOOL DISTRICT



59

CELEBRATION SCHOOL
OSCEOLA COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: New K-12 School
FACILITY NAME & ADDRESS:
Celebration Schools
851 Celebration Avenue
Celebration, FL 34747
(407) 566-2300
OWNER, CONTACT PERSON & PHONE NUMBER:
Osceola County Public Schools
John P. Davis
701 Simpson Road, Suite 1
Kissimmee, FL 34744
(407) 344-5020
ARCHITECT, ADDRESS & PHONE NUMBER:
Schenkel Shultz
200 E. Robinson Street, Suite 300
Orlando , FL 32801
(407) 872-3322
CONTRACTOR, ADDRESS & PHONE NUMBER:
Centex Rooney Construction Company
9025 Boggy Creek Road, Suite 2
Orlando, FL 32804
(407) 856-7619
CONSTRUCTION CONTRACT DATE: May 1996
OCCUPANCY DATE: February 1997
SITE SIZE: 38 Acres
BUILDING AREA: 188,968 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 12
STUDENT CAPACITY: 1,069
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $24,139,966

GENERAL DESCRIPTION OF FACILITY: A one and two story facility consisting of: 10 Classrooms, 3 Science Labs, Art, 2 Music Labs, Gym, Administration, Library /Media, Cafetorium, and Kitchen,
SPECIAL FEATURES or COMMENTS: Classrooms are in neighborhoods. Special features include the CCTV Studio, Black Box Theater, wetlands boardwalk, and Imagineering Lab.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, covered play area, baseball field, softball field, tennis courts, landscaping, and courtyards.
FLOORS: Concrete slab on grade. Second floor - reinforced poured concrete.
ROOF: Metal roofing on pemb. system.
EXTERIOR WALLS: Concrete masonry units and stucco.
INTERIOR WALLS: Painted concrete masonry units.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, quarry tile, and wood.
BASE: Vinyl, rubber, ceramic tile, and quarry tile.
CEILINGS: 2x2 and 2x4 lay-in acoustical tile, gypsum board, and exposed.
HVAC: Air cooled chiller, cooling tower, chilled water system, heat pump, VAV boxes, and individual units.
PLUMBING: Municipal water and sewer. PVC and cast iron sewage drainage system. Fire sprinkler system. Natural gas.
ELECTRICAL: Fluorescent and HID light fixtures, telephone, CCTV, fire alarm, security, emergency generator, fiber optics, computer networking, and energy management.

CELEBRATION SCHOOL
OSCEOLA COUNTY PUBLIC SCHOOLS



61

KISSIMMEE MIDDLE SCHOOL
OSCEOLA COUNTY PUBLIC SCHOOLS



TYPE OF FACILITY: New Middle School
FACILITY NAME & ADDRESS:
Kissimmee Middle School
2410 Dyer Boulevard
Kissimmee, FL 34741
(407) 870-0857
OWNER, CONTACT PERSON & PHONE NUMBER:
Osceola County Public Schools
John P. Davis
701 Simpson Road, Suite 1
Kissimmee, FL 34744
(407) 344-5020
ARCHITECT, ADDRESS & PHONE NUMBER:
Schenkel Shultz Architects
200 E. Robinson, Suite 300
Orlando, FL 32801
(407) 872-3322
CONTRACTOR, ADDRESS & PHONE NUMBER:
M. M. Parrish Construction Company
175 5 Street SW, Suite 104
Winter Haven, FL 33883
(813) 297-5907
CONSTRUCTION CONTRACT DATE: May 1995
OCCUPANCY DATE: February 1997
SITE SIZE: 25 Acres
BUILDING AREA: 117,821 Sq. Ft.
GRADE LEVEL ORGANIZATION: 6 - 8
STUDENT CAPACITY: 900
TOTAL CONSTRUCTION COST: (includes site improve., site aquisition, & fees as applicable):
$14,813,295

GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 14 Classrooms, 6 Resource Rooms, 2 Skills Labs, 5 Science Labs, 2 ESE Classrooms, Art, 3 Music Labs, 6 Vo-tech Labs, Gym, Administration, Library/Media, Cafetorium, and Kitchen.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, baseball field, softball field, basketball courts, tennis courts, landscaping, and courtyards
FLOORS: Concrete slab on grade. Second floor poured concrete.
ROOF: Metal roofing on rigid insulation and metal decking.
EXTERIOR WALLS: Concrete masonry units with split face block veneer.
INTERIOR WALLS: Concrete masonry units
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, quarry tile, poured resilient, and wood.
BASE: Vinyl, ceramic tile, and quarry tile.
CEILINGS: 2x2 and 2x4 lay-in acoustical tile, exposed.
HVAC: Chilled water system with VAV boxes and cooling tower.
PLUMBING: Municipal water and sewer. Copper water distribution system. Cast iron sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, fiber optics, computer networking, and energy management.

KISSIMMEE MIDDLE SCHOOL
OSCEOLA COUNTY PUBLIC SCHOOLS



63

BROOKER CREEK ELEMENTARY SCHOOL
PINELLAS COUNTY SCHOOLS



TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Brooker Creek Elementary School
3102 Forelock Road
Tarpon Springs, FL 34689
(813) 943-4600
OWNER, CONTACT PERSON & PHONE NUMBER:
Pinellas County Schools
Tony Rivas, Director, Facilities
11111 S. Belcher Road
Largo, FL 33773
(813) 547-7165
ARCHITECT, ADDRESS & PHONE NUMBER:
Edward C. Hoffman, Jr., Architect, AIA, PA
29 W. Orange Street
Tarpon Springs, FL 34689
(813) 938-2835
CONTRACTOR, ADDRESS & PHONE NUMBER:
The Norwood Company
5584 Rio Vista Drive
Clearwater, FL 33760
(813) 536-8669
CONSTRUCTION CONTRACT DATE: July 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 29.4 Acres
BUILDING AREA: 86,030 Sq. Ft.
GRADE LEVEL ORGANIZATION: K - 5
STUDENT CAPACITY: 760
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $7,953,646

GENERAL DESCRIPTION OF FACILITY: A one and two story facility consisting of: 28 Classrooms, 1 Resource Room, 1 Skills Lab, 4 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: A compact prototype school with a contained, single "Main Street" circulation space terminating at the "Town Square" courtyard with an amphitheater.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, basketball courts, play fields, landscaping, courtyards, and outdoor stage
FLOORS: Concrete slab on grade. Second floor - precast planks.
ROOF: Metal roof on metal deck with rigid insulation. Built-up roof on metal deck with light weight concrete.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Painted concrete masonry units
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl
CEILINGS: 2x2 and 2x4 lay-in acoustical tile, gypsum board, and exposed.
HVAC: Air cooled chiller, chilled water system, and VAV boxes.
PLUMBING: Municipal water and sewer. Copper water distribution service. PVC sewage drainage system. Natural gas.
ELECTRICAL: Fluorescent light fixtures, telephone, fire alarm, intercom, security, emergency generator, fiber optics, computer networking, and energy management.

BROOKER CREEK ELEMENTARY SCHOOL
PINELLAS COUNTY SCHOOLS



65

McMULLEN BOOTH ELEMENTARY SCHOOL
PINELLAS COUNTY SCHOOLS



TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
McMullen Booth Elementary School
3025 Union Street
Clearwater, FL 34619
(813) 943-4600
OWNER, CONTACT PERSON & PHONE NUMBER:
Pinellas County Schools
Tony Rivas, Director, Facilities
11111 S. Belcher Road
Largo, FL 33773
(813) 547-7165
ARCHITECT, ADDRESS & PHONE NUMBER:
Edward C. Hoffman, Jr., Architect, AIA, PA
29 W. Orange Street
Tarpon Springs, FL 34689
(813) 938-2835
CONTRACTOR, ADDRESS & PHONE NUMBER:
Ellis Construction Company, Inc.
1714 Cypress Street
Tampa, FL 33606
(813) 251-8473
CONSTRUCTION CONTRACT DATE: May 1996
OCCUPANCY DATE: July 1997
SITE SIZE: 19 Acres
BUILDING AREA: 95,606 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 5
STUDENT CAPACITY: 830
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $8,957,923

GENERAL DESCRIPTION OF FACILITY: A one and two story facility consisting of: 34 Classrooms, 1 Resource Room, 1 Skills Labs, 4 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: A compact, prototype school with a contained, single "Main Street" circulation space terminating at the "Town Square" courtyard with an amphitheater.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, basketball courts, landscaping, courtyards, and outdoor stage.
FLOORS: Concrete slab on grade. Second floor - precast planks.
ROOF: Metal roof on metal deck with rigid insulation. Built-up roof on metal deck with light weight concrete.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Painted concrete masonry units.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl
CEILINGS: 2x2 and 2x4 lay-in acoustical tile, gypsum board, and exposed.
HVAC: Air cooled chiller, chilled water system, and VAV boxes.
PLUMBING: Municipal water and sewer. PVC sewage drainage system. Natural gas.
ELECTRICAL: Fluorescent light fixtures, telephone, fire alarm, intercom, security, emergency generator, fiber optics, computer networking, and energy management.

McMULLEN BOOTH ELEMENTARY SCHOOL
PINELLAS COUNTY SCHOOLS



67

JOHN M. SEXTON ELEMENTARY SCHOOL
PINELLAS COUNTY SCHOOLS

TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
John M. Sexton Elementary School
1717 54th Ave., N
St. Petersburg, FL 33714
(813) 570-3400
OWNER, CONTACT PERSON & PHONE NUMBER:
Pinellas County Schools
Tony Rivas, Director, Facilities
11111 S. Belcher Road
Largo, FL 33773
(813) 547-7165
ARCHITECT, ADDRESS & PHONE NUMBER:
Edward C. Hoffman, Jr., Architect, AIA, PA
29 W. Orange Street
Tarpon Springs, FL 34689
(813) 938-2835
CONTRACTOR, ADDRESS & PHONE NUMBER:
Ellis Construction Company, Inc.
1714 Cypress Street
Tampa, FL 33606
(813) 251-8473
CONSTRUCTION CONTRACT DATE: May 1996
OCCUPANCY DATE: August 1997
SITE SIZE: 12.7 Acres
BUILDING AREA: 95,606 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 5
STUDENT CAPACITY: 838
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $8,413,963

GENERAL DESCRIPTION OF FACILITY: A one and two story facility consisting of: 34 Classrooms, 1 Resource Room, 1 Skills Lab, 4 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, Kitchen, and Multipurpose Room.
SPECIAL FEATURES or COMMENTS: A compact, prototype school with a contained, single "Main Street" circulation space terminating at the "Town Square" courtyard with an amphitheater.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, basketball courts, landscaping, courtyards, and outdoor stage.
FLOORS: Concrete slab on grade. Second floor - precast planks.
ROOF: Metal roof on metal deck with rigid insulation. Built-up roof on metal deck with light weight concrete.
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Painted concrete masonry units.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl
CEILINGS: 2x2 and 2x4 lay-in acoustical tile, gypsum board, and exposed.
HVAC: Air cooled chiller, chilled water system, and VAV boxes.
PLUMBING: Municipal water and sewer. Copper water distribution pipes. PVC sewage drainage system. Natural gas.
ELECTRICAL: Fluorescent light fixtures, telephone, fire alarm, intercom, security, emergency generator, fiber optics, computer networking, and energy management.

JOHN M. SEXTON ELEMENTARY SCHOOL
PINELLAS COUNTY SCHOOLS



69

WICKLOW ELEMENTARY SCHOOL
SEMINOLE COUNTY PUBLIC SCHOOLS

TYPE OF FACILITY: New Elementary School
FACILITY NAME & ADDRESS:
Wicklow Elementary School
100 Lake Placid Drive
Sandford, FL 32771
(407) 320-1250
OWNER, CONTACT PERSON & PHONE NUMBER:
Seminole County Public Schools
Dianne Kramer
400 E. Lake Mary Boulevard
Sanford, FL 32773
(407) 320-0063
ARCHITECT, ADDRESS & PHONE NUMBER:
Schenkel Shultz
200 E. Robinson Street, Suite 300
Orlando, FL 32801
(407) 872-3322
CONTRACTOR, ADDRESS & PHONE NUMBER:
Thurman Construction Company
491 S. R. 434 North
Altamonte Springs, FL 32714
(407) 862-2889
CONSTRUCTION CONTRACT DATE: August 1996
OCCUPANCY DATE: September 1997
SITE SIZE: 16 Acres
BUILDING AREA: 117,314 Sq. Ft.
GRADE LEVEL ORGANIZATION: Pre-K - 5
STUDENT CAPACITY: 894
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $9,000,000

GENERAL DESCRIPTION OF FACILITY: A one story facility consisting of: 32 Classrooms, 5 Resource Rooms, 2 Skills Labs, 4 ESE Classrooms, Art, Music, Administration, Library/Media, Stage, Cafetorium, and Kitchen.
SPECIAL FEATURES or COMMENTS: Very cost effective design includes flexibility in customizing interior spaces, security, and simple construction methods.
SITE DEVELOPMENT: Asphalt drives and parking. Parent drop-off, bus drop-off, play fields, covered play area, and landscaping.
FLOORS: Concrete slab on grade,
ROOF: Single ply and metal roofing on metal deck with rigid insulation.
EXTERIOR WALLS: Concrete masonry units with brick.
INTERIOR WALLS: Concrete masonry units. Metal studs with gypsum board in administration.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and quarry tile.
BASE: Vinyl and ceramic tile.
CEILINGS: 2x4 lay-in acoustical tile and gypsum board
HVAC: Air cooled chiller, heat strips, chilled water system, VAV boxes.
PLUMBING: Municipal water supply. Copper water distribution pipes. PVC and cast iron sewage drainage system. LP-gas.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, intercom, security, emergency generator, computer networking, and energy management.

70

WICKLOW ELEMENTARY SCHOOL
SEMINOLE COUNTY PUBLIC SCHOOLS



BEST COPY AVAILABLE

BUILDING NUMBER 6
DAYTONA BEACH COMMUNITY COLLEGE

TYPE OF FACILITY: New Classroom/Laboratory Building and Tele-Conference Center
FACILITY NAME & ADDRESS:
Building No. 6, Classroom Laboratory Building & Tele-Conference Center
Daytona Beach Community College
Deland, FL
OWNER, CONTACT PERSON & PHONE NUMBER:
Daytona Beach Community College
Dr. John E. Justus
1200 International Speedway Boulevard
Daytona Beach, FL 32114
(904) 254-3078
ARCHITECT, ADDRESS & PHONE NUMBER:
Strollo Architects, Incorporated
68 South Ivanhoe Boulevard
Orlando, FL 32804
(407) 423-5355
CONTRACTOR, ADDRESS & PHONE NUMBER:
Arnold Construction Co., Inc.
2929 Wadsworth Avenue
Orlando, FL 32806
(407) 422-8444
CONSTRUCTION CONTRACT DATE: June 1994
OCCUPANCY DATE: 1995
SITE SIZE: 4 Acres
BUILDING AREA: 32,000 Sq. Ft.
GRADE LEVEL ORGANIZATION: Community College
STUDENT CAPACITY: 185

TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $3,200,000.00
GENERAL DESCRIPTION OF FACILITY: A two story facility providing program space for: Computer, Foreign Language, Physics, Micro-Biology, Law Enforcement, Emergency Medical, Nursing, IMTS, Cosmetics Labs and related classroom spaces.
SPECIAL FEATURES OR COMMENTS: The design addressed the need for multi-purpose space through a stand alone Tele-Conference Center. The building is also designed to house student services.
SITE DEVELOPMENT: Over excavate and recompact fill.
FLOORS: Concrete slab-on-grade. Second floor - concrete on metal deck over bar joists.
ROOF: Single-ply membrane over tapered insulation.
EXTERIOR WALLS: Concrete masonry units with brick and stucco.
INTERIOR WALLS: Concrete masonry units and special coating on drywall.
FLOOR FINISHES: Carpet, vinyl composition tile, and ceramic tile.
BASE: Rubber
CEILINGS: Acoustical tile and painted plaster.
HVAC: Central plant, C.W. & H.W.
PLUMBING: Cast iron, acid resistant PVC and copper piping. Electric hot water heaters.
ELECTRICAL: Performance lighting and sound system, fiber optics MIS system and Satellite/GOAA DISH.

BUILDING NUMBER 6
DAYTONA BEACH COMMUNITY COLLEGE



73

L. GALE LEMERAND HEALTH, WELLNESS, & COMMUNITY EDUCATION CENTER
DAYTONA BEACH COMMUNITY COLLEGE

TYPE OF FACILITY: New Wellness Center
FACILITY NAME & ADDRESS:
L. Gale Lemerand Health, Wellness, & Community Education Center
Daytona Beach Community College
1200 W. International Speedway Blvd.
Daytona Beach, FL 32114
(904) 255-8131
OWNER, CONTACT PERSON & PHONE NUMBER:
Daytona Beach Community College
John E. Justus
1200 W. International Speedway Blvd.
Daytona Beach, FL 32114
(904) 254-3078
ARCHITECT, ADDRESS & PHONE NUMBER:
Schenkel Shultz, Inc.
200 E. Robinson Street, Suite 300
Orlando, FL 32801
(407) 872-3322
CONTRACTOR, ADDRESS & PHONE NUMBER:
Strickland and Thompson, A Joint Venture
541 South Orlando Ave., Suite 302
Maitland, FL 32751
(407) 647-7715
CONSTRUCTION CONTRACT DATE: April 1996
OCCUPANCY DATE: August 1997
BUILDING AREA: 55,374 Sq. Ft.
GRADE LEVEL ORGANIZATION: Community College

TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $6,200,000
GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 4 Classrooms, Gym, Physical Therapy & Swimming Pool
SPECIAL FEATURES or COMMENTS: The 25 meter swimming pool is totally enclosed and accommodates the handicapped.
SITE DEVELOPMENT: Landscaping
FLOORS: Concrete slab on grade.
ROOF: Metal roof deck with single ply and metal roofing.
EXTERIOR WALLS: Concrete masonry units with brick and EIFIS.
INTERIOR WALLS: Concrete masonry units and metal studs with gypsum board.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, quarry tile, poured resilient, and wood at gym.
BASE: Vinyl
CEILINGS: 2x2 lay-in acoustical tile
HVAC: Water cooled chiller.
PLUMBING: Municipal water and sewer. Copper water distribution system. PVC and cast iron sewage drainage system. Natural gas.
ELECTRICAL: Fluorescent and HID light fixtures, telephone, CCTV, fire alarm, fiber optics, computer networking, and energy management.

L. GALE LEMERAND HEALTH, WELLNESS, & COMMUNITY EDUCATION CENTER
DAYTONA BEACH COMMUNITY COLLEGE



NEW COMMUNITY COLLEGE CENTER
EDISON COMMUNITY COLLEGE

TYPE OF FACILITY: New community college center.
FACILITY NAME & ADDRESS:
Edison Community College, Charlotte County Center
26300 Airport Road
Punta Gorda, FL 33950
OWNER, CONTACT PERSON & PHONE NUMBER:
Edison Community College
Ron White, Director of Facilities
8099 College Parkway (P. O. Box 60210)
Ft. Myers, FL 33906-6210
(941) 489-9243
ARCHITECT, ADDRESS & PHONE NUMBER:
Barany-Schmitt-Weaver & Partners, Inc.
1520 Royal Palm Square Boulevard
Ft. Myers, FL 33919
(941) 278-3838.
CONTRACTOR, ADDRESS & PHONE NUMBER:
Sovan Construction Company, Inc.
7151 University Boulevard
Winter Park, FL 32792
(407) 677-6555
CONSTRUCTION CONTRACT DATE: December 1994
OCCUPANCY DATE: March 1997
SITE SIZE: 204 Acres
BUILDING AREA: 151,823 Sq. FT.
GRADE LEVEL ORGANIZATION: Community College
STUDENT CAPACITY: 2,011
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $22,443,330
GENERAL DESCRIPTION OF FACILITY: A campus of 11-one story and 1-two story buildings which house 22 classrooms, 23 labs, art, observatory, allied health, child care, learning resources, physical fitness, faculty offices, administration, auditorium, theatrical stage, student services, plant operations, and maintenance.
SPECIAL FEATURES or COMMENTS: The campus is framed with lakes, woods, and landscaping to provide picturesque views. The linear campus plan is designed around a central walkway spine. Parking and entry points are placed along the spine for ease of access and separation of vehicles and pedestrians. The building design makes a simple, uncomplicated statement which will remain timeless and distinctive.
SITE DEVELOPMENT: Asphalt drives and parking, concrete walks. Tennis courts, handball courts, volleyball courts and basketball courts.
FLOORS: Concrete slab on grade. Second floor - reinforced concrete slab over precast concrete slabs.
ROOF: Metal roof deck and rigid insulation on steel purlins and rigid frame. Standing seam copper and built-up roofing.
EXTERIOR WALLS: Ground - Concrete masonry units with brick. Upper walls - metal framing and brick.
INTERIOR WALLS: Painted concrete masonry units and gypsum drywall over steel framing.
FLOOR FINISHES: Carpet, ceramic tile, resilient flooring, urethane flooring, hardwood flooring and seamless epoxy flooring.
BASE: Rubber
CEILINGS: Suspended acoustical tile and plaster.
HVAC: Air cooled chillers, central chilled water system, air-handling units, and VAV boxes.
PLUMBING: Combination PVC and copper lines.
ELECTRICAL: A 480V, 3 pole, 4 wire primary service system. Internal service is reduced by dry type transformers. Communication/data systems are combination of fiber optic and copper wire.

NEW COMMUNITY COLLEGE CENTER
EDISON COMMUNITY COLLEGE



77

WILLIAM A. SEEKER CAMPUS
FLORIDA KEYS COMMUNITY COLLEGE

TYPE OF FACILITY: Replacement of classrooms, library, and administration.
FACILITY NAME & ADDRESS:
Florida Keys Community College
5901 W. College Road
Key West, FL 33040
(305) 296-9081
OWNER, CONTACT PERSON & PHONE NUMBER:
Florida Keys Community College
Leigh Smith, Dean of Business
5901 W. College Road
Key West, FL 33040
(305) 292-5152
ARCHITECT, ADDRESS & PHONE NUMBER:
Bender & Associates Architects
1503 Government Road
Key West, FL 33040
(305) 296-1347
CONTRACTOR, ADDRESS & PHONE NUMBER:
Brown & Root Building Company
5830 142nd Avenue, North
Clearwater, FL 34620
(813) 539-7668
CONSTRUCTION CONTRACT DATE: March 1995
OCCUPANCY DATE: January 1997
SITE SIZE: 14 Dry Acres
BUILDING AREA: 85,000 Sq. Ft.

GRADE LEVEL ORGANIZATION: Community College
STUDENT CAPACITY: 10,000
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $18,000,000
GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 30 Classrooms, 3 Resource Rooms, 1 Skills Lab, 4 Science Labs, 4 Art Labs, 3 Vo-tech Labs, Administration, and Library/Media.
SITE DEVELOPMENT: Asphalt drives and parking.
FLOORS: Poured concrete.
ROOF: Metal roof and deck with rigid insulation
EXTERIOR WALLS: Concrete masonry units with stucco finish.
INTERIOR WALLS: Concrete masonry units and metal studs with gypsum board.
FLOOR FINISHES: Carpet, vinyl composition tile, and ceramic tile.
BASE: Rubber and ceramic tile.
CEILINGS: 2x4 lay-in acoustical tile
HVAC: Chilled water system and VAV boxes
PLUMBING: Municipal water and private sewage treatment plant. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, CCTV, fire alarm, emergency generator, computer networking, and energy management.

WILLIAM A. SEEKER CAMPUS
FLORIDA KEYS COMMUNITY COLLEGE

79

MARTIN AND PAT FINE CENTER FOR THE ARTS
MIAMI-DADE COMMUNITY COLLEGE, KENDALL CAMPUS



TYPE OF FACILITY: New Center for the Arts
FACILITY NAME & ADDRESS:
Martin and Pat Fine Center for the Arts
11011 SW 104th Street
Miami, FL 33176-3393
(305) 237-2000
OWNER, CONTACT PERSON & PHONE NUMBER:
Miami-Dade Community College
Alan Kaplan, P.E.
Kendall Campus-Building L-110
11011 SW 104th Street
Miami, FL 33176-3393
(305) 237-2000
ARCHITECT, ADDRESS & PHONE NUMBER:
Spillis Candela & Partners, Inc.
800 Douglas Entrance
Coral Gables, FL 33134
(305) 444-4691
CONTRACTOR, ADDRESS & PHONE NUMBER:
Stobbs Brothers
580 N.E. 92nd Street
Miami Shores, FL 33138
(305) 751-1692
CONSTRUCTION CONTRACT DATE: October 1994
OCCUPANCY DATE: January 1997
SITE SIZE: 4.0 Acres
BUILDING AREA: 96,000 Sq. Ft.

GRADE LEVEL ORGANIZATION: Community College
STUDENT CAPACITY: 675
TOTAL CONSTRUCTION COST: (includes site improve): $12,290,000.00
GENERAL DESCRIPTION OF FACILITY: A three story facility consisting of: Administration, Library/Media, Auditorium, and Stage.
SPECIAL FEATURES or COMMENTS: Black box theater, sound recording studio, and art studio spaces.
SITE DEVELOPMENT: Asphalt drives and parking
FLOORS: Concrete slab on grade,
ROOF: Light weight concrete roof deck with built-up roofing.
EXTERIOR WALLS: Concrete masonry units with stucco and precast concrete.
INTERIOR WALLS: Concrete masonry units and metal studs, gypsum board, and veneer plaster.
FLOOR FINISHES: Carpet, vinyl composition tile, ceramic tile, and terrazzo.
BASE: Vinyl and ceramic tile
CEILINGS: 2x2 lay-in acoustical tile, plaster, gypsum board, and exposed.
HVAC: Chilled water system and VAV boxes.
PLUMBING: Municipal water and sewer. Natural gas.
ELECTRICAL: Fluorescent, HID, and theatrical light fixtures, telephone, CCTV, fire alarm, emergency generator, fiber optics, computer networking, and energy management.

MARTIN AND PAT FINE CENTER FOR THE ARTS
MIAMI-DADE COMMUNITY COLLEGE, KENDALL CAMPUS



81

TEACHING ZOO
SANTA FE COMMUNITY COLLEGE

TYPE OF FACILITY: New Teaching Zoo
FACILITY NAME & ADDRESS:
Teaching Zoo - Santa Fe Community College
3000 NW 83rd Street
Gainesville, FL 32606
(352) 395-5521
OWNER, CONTACT PERSON & PHONE NUMBER:
Santa Fe Community College
Greg Nuetzi, Director of Facilities
3000 NW 83 Street
Gainesville, FL 32606-6200
(352) 395-5521
ARCHITECT, ADDRESS & PHONE NUMBER:
Craig Salley & Associates
3911 Newberry Road
Gainesville, FL 32607
(352) 372-8424
CONTRACTOR, ADDRESS & PHONE NUMBER:
D. E. Wallace Construction Corp.
P. O. Box 1300
Alachua, FL 32616
(352) 462-0141
CONSTRUCTION CONTRACT DATE: May 1996
OCCUPANCY DATE: March 1997
SITE SIZE: 8 Acres
BUILDING AREA: 13,440 Sq. Ft.
GRADE LEVEL ORGANIZATION: Community College
STUDENT CAPACITY: 13,000 (Total Campus)
TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable):
$2,162,196.00

GENERAL DESCRIPTION OF FACILITY: Four - one story buildings consisting of: an Administration Building, Reptile House, Quarantine Building, and Classroom / Laboratory Building with Amphitheater.
SPECIAL FEATURES or COMMENTS: The complex consists of four buildings including an office building with multi- purpose flexibility; a reptile house; a quarantine building where animals are examined for diseases; and a laboratory/classroom with an attached open-air amphitheater. The zoo serves as the country's only college-accredited teaching zoo.
SITE DEVELOPMENT: Bus drop-off, landscaping, and mulch paths for zoo visitors and tours.
FLOORS: Concrete slab on grade.
ROOF: Metal deck and roofing.
EXTERIOR WALLS: Hardiboard
INTERIOR WALLS: Metal studs with veneer plaster
FLOOR FINISHES: Carpet and ceramic tile.
BASE: Vinyl and ceramic tile.
CEILINGS: 2x2 lay-in acoustical tile
HVAC: Temperature and humidity controlled by 100% outdoor air dehumidifiers by Dectrol, Inc., DK-010; Lennox HP-25 Heat Pump. 10-15 room air changes per hour for animals.
PLUMBING: Municipal water. PVC sewage drainage system.
ELECTRICAL: Fluorescent light fixtures, telephone, fire alarm, intercom, security, fiber optics, and computer networking.

TEACHING ZOO
SANTA FE COMMUNITY COLLEGE



BEST COPY AVAILABLE

83

STUDENT SERVICES BUILDING
VALENCIA COMMUNITY COLLEGE



TYPE OF FACILITY: New Student Services Building
FACILITY NAME & ADDRESS:
Student Services Building
Valencia Community College - West Campus
1800 S. Kirkman Road
Orlando, FL 32811
(407) 299-5000
OWNER, CONTACT PERSON & PHONE NUMBER:
Valencia Community College
James Reinschmidt
1800 S. Kirkman Road
Orlando, FL 32811
(407) 299-5000 Ext 1708
ARCHITECT, ADDRESS & PHONE NUMBER:
Hunton Brady Pryor Maso Architects, P.A.
135 West Central Boulevard, Suite 400
Orlando, Fl 32801
(407) 839-0886
CONTRACTOR, ADDRESS & PHONE NUMBER:
H. J. High Construction Company
1015 West Amelia Street
Orlando, Fl 32805
(407) 422-8171
CONSTRUCTION CONTRACT DATE: March 1994
OCCUPANCY DATE: January 1996
SITE SIZE: 160 Acres (Total campus)
BUILDING AREA: 70,000 Sq. Ft.
GRADE LEVEL ORGANIZATION: Community College
STUDENT CAPACITY: 700

TOTAL CONSTRUCTION COST: (includes site improve., site acquisition, furn & equip, & fees as applicable): $9,000,000
GENERAL DESCRIPTION OF FACILITY: A two story facility consisting of: 4 Classrooms, 2 Resource Rooms, Administration, Counseling Offices, Office for Students with Disabilities, Career Development, Tutorial Services, Admissions, Registration, Records, Financial Aid, Finance, Communication, and Campus Security.
SPECIAL FEATURES or COMMENTS: This two-story atrium building is the most prominent building on the campus and is the main focal point upon entry to the campus.
SITE DEVELOPMENT: Asphalt drives and parking. Landscaping and courtyard.
FLOORS: Concrete slab on grade. Second floor - reinforced poured concrete.
ROOF: Built-up roof on concrete roof deck.
EXTERIOR WALLS: Steel studs, precast concrete brick
INTERIOR WALLS: Metal studs with gypsum board.
FLOOR FINISHES: Carpet, vinyl composition tile, and ceramic tile.
BASE: Vinyl
CEILINGS: 2x2 and 2x4 lay-in acoustical tile and gypsum board.
HVAC: Air cooled chiller, heat strips, VAV boxes.
PLUMBING: Municipal water. PVC sewage drainage system.
ELECTRICAL: Fluorescent and HID light fixtures, telephone, CCTV, fire alarm, security, and computer networking,

STUDENT SERVICES BUILDING
VALENCIA COMMUNITY COLLEGE

LEGEND
1 LOGGIA
2 EXHIBITION
3 RECEPTION
4 CUSTOMER SERVICE
5 OFFICE
6 COUNSELOR'S OFFICE
7 SPECIALIST'S OFFICE
8 ANALYST'S OFFICE
9 SECRETARY
10 CONFERENCE ROOM
11 TESTING
12 CLASSROOM
13 TOILET ROOM
14 STORAGE
15 FILES / RECORDS
16 WORK ROOM
17 REGISTRATION
18 SCHEDULING
19 MICROFILM
20 RECORDS OFFICE
21 TAPE ROOM
22 LOCKERS
23 MECHANICAL ROOM



BEST COPY AVAILABLE

NEW FACILITIES CONTRACTED IN 1997

District Name	Facility Name	Square Feet	Total Cost
Bradford	New Starke Elementary	92,569	$10,959,266
Brevard	Longleaf Elementary	93,870	$8,217,452
Broward	New Elementary G-6	114,722	$12,178,600
Broward	New Elementary O-91	114,722	$11,800,204
Broward	New Elementary K-91	114,722	$11,800,204
Broward	New Panther Run Elementary	114,722	$11,800,204
Charlotte	Kingsway Elementary	120,481	$9,677,141
Dade	Gladeview Academy	44,178	$5,815,619
Dade	Caribbean Elementary	95,290	$10,200,296
Dade	Linda Lentin Elementary	92,000	$10,748,837
Duval	New Elementary "S"	120,481	$11,266,133
Duval	New Elementary "Q"	120,481	$10,295,651
Hillsborough	Westchase Elementary	91,165	$10,439,530
Hillsborough	Anthony Pizzo Elementary	108,200	$11,346,609
Hillsborough	Marion S. Rodgers Middle	156,706	$18,115,094
Hillsborough	Clark Elementary "B"	88,176	$10,580,966
Hillsborough	Riverview High "EEE"	285,732	$41,254,292
Lake	Eustis Middle School "BB"	94,454	$13,793,173
Lee	J Colin English Elementary	96,627	$9,594,293
Lee	Diplomat Middle "CC"	146,352	$14,052,256
Leon	New Elementary "I"	126,995	$12,767,663
Leon	Canopy Oaks High "AAA"	253,137	$40,960,967
Orange	Riverdale Elementary "V"	114,160	$11,676,691
Orange	Lake Gem Elementary "W"	106,851	$11,184,312
Orange	Pinewood Elementary "X"	106,851	$11,565,045
Orange	Lake George Elementary "Y"	106,851	$11,494,943
Orange	Lakeville Elementary "Z"	114,160	$11,398,563
Orange	Corner Lake Middle	184,439	$26,267,980
Orange	Meadow Woods Middle	184,439	$25,271,072
Osceola	Gateway High 9th Grade Center	32,638	$4,855,162
Palm Beach	Highland Elementary	96,601	$12,629,691
Palm Beach	Lincoln Elementary	166,798	$15,267,972
Pasco	Wesley Chapel High	190,000	$20,966,572
Pasco	Sand Pine Elementary	84,552	$7,642,347
Pasco	J W Mitchell Senior High	190,000	$20,893,570
St. Lucie	C.A. Moore Elementary	103,434	$9,000,191
St. Lucie	St. Lucie West Middle "DD"	159,092	$16,636,627
St. Lucie	Savannah Ridge Elementary	101,074	$9,458,851
Santa Rosa	Thomas L. Sims Middle	103,400	$6,962,127
Volusia	Middle School "CC"	168,171	$17,685,315

COST OF CONSTRUCTION FOR FLORIDA EDUCATIONAL FACILITIES

Public Schools Categories		**1996 Cost** (per sq. Ft.)
	Contract Cost	Total Cost
Elementary School	$83.00	$101.55
Middle School	$99.07	$116.81
High School	$106.20	$134.88
Vo-Tech Center	$106.20	$134.88
Relocatable Classroom (1/2 Average School Cost)	$48.88	$55.86
Ancillary Facility	$98.74	$111.72

Post Secondary Categories	**1997 Cost (per sq. Ft.)**
Classrooms	$125.61
Teaching Labs	$121.85
Research Labs	$131.29
Library	$90.82
Office	$114.42
Auditorium/Exhibits	$124.56
Student Services	$110.76
Gymnasium	$123.41
Support Services	$90.61
Instructional Media	$136.54



Florida Department of Education
Tallahassee, Florida
Frank T. Brogan Commissioner